



READY STACK™: RackReady® data halls

Facility Size: 113,000 sq. ft.


For Inquiries

sales@stackinfra.com

+1-888-316-8177

NAL01 DATA CENTER
MULTI-TENANT COLOCATION SUITES

Property Overview



CAPACITY

Facility Size

- 113,000 sq. ft.

Total Capacity

- 2.4 MW

Deployments

- READY STACK™; RackReady® data halls

COOLING & EFFICIENCY

Cooling

- 2(N+1) Chilled water system, N+4 AHUs

Efficiency

- Full waterside and air side economization

Cooling Reserve

- Multiple make up water sources
- 25 minute thermal water storage

Density

- High density deployments supported in excess of 25 kW per cabinet.
- Water cooling at the rack level also available for higher densities

SAFETY & SECURITY

Security

- Dual-factor biometric access
- CCTV coverage with 93-day retention
- Perimeter fencing

Fire Detection

- Dual smoke detection including VESDA

Fire Suppression

- Double interlock preaction sprinkler fire suppression systems

AMENITIES

Work Space

- Conference and break rooms
- Complimentary WiFi

Storage

- Shared and private storage/staging

Client Conveniences

- Showers
- Bicycle Storage

POWER & RELIABILITY

Utility Service

- Diverse and redundant utility feeds

Generators

- 2N redundancy

Fuel Storage

- Minimum 48 hours of operation

UPS

- 2(N+1) UPS configuration

PDU

- 2N PDU configuration

BMS Controls

- Client access to BMS Portal

Building Hardening

- 250 MPH wind-rated shell

CONNECTIVITY

Diversity

- 2 Meet-Me-Rooms with diverse fiber entrances

Carrier Availability

- 4 carriers on site
- Carrier neutral

Additional Connectivity

- Roof space available